









Stainless Frame

Integrated Frame

Integrated Solid

Key Features

- Convection cooling system provides a quick cool down and consistent temperature
- Black interior
- LowE coated, argon gas filled, dual thermopane glass door provides protection from harmful UV Light
- Stainless steel full-wrap door and handle (1/8" diameter)
- Stainless steel grille (stainless model), black metal grille (integrated models)
- Two, three-quarter extension, black wine racks
- Two adjustable tempered glass shelves

- Digital touch pad control
- Temperature range: 34°F to 60°F
- Bright white LED lighting
- Volume of 2.9 cu ft holds up to 8 wine bottles (750 ml), and 48 bottles (12 oz) or 60 cans (12 oz)
- Field reversible door is shipped right-hand hinged
- Built-in or freestanding
- Four adjustable leveling legs


Model Details


Model	Voltage/Hz	Door Swing	Finish	Shipping Weight
UHBV115-SG01A	115 / 60	Field Reversible	Stainless Frame	96 lb
UHBV115-IG01A	115 / 60	Field Reversible	Integrated Frame	93 lb
UHBV115-IS01A	115 / 60	Field Reversible	Integrated Solid	89 lb



14 ½6" (379 mm) 28" (711 mm) 34 ½" to 35 ½" (867 mm to 892 mm)

Front







Top

Specifications

Model	HBV115		
Amps: Running (115 v)	1.2 A		
Capacity Bottle	48		
Capacity Can	60		
Capacity: Total Volume (cu ft)	2.9 cu ft		
Capacity: Wine Bottle (750 ml)	8		
Dimensions: Product Depth	22 ¹ / ₄ " / 562 mm		
Dimensions: Product Height	34 ½" / 867 mm		
Dimensions: Product Width	14 ¹⁵ / ₁₆ " / 379 mm		
ENERGY STAR (Glass)	No		
ENERGY STAR (Solid)	Tier 3		
Energy Consumption: Avg. Per Year	285 kWh		
Panel Height	30 ½" / 768 mm		
Panel Thickness	³ / ₄ " / 20 mm		
Panel Type	2 ³ / ₄ " / 70 mm Frame or Solid Panel		
Panel Width	14 ¾" / 375 mm		
Refrigerant Type	R600a		
Sabbath (Star K Certified)	Yes		
Temperature Range	34°F to 60°F		



Cabinet Cut-Out



Warranty

- 1 Year (parts & labor) / 5 year sealed system (parts)
- + Additional 1 Year (parts & labor) warranty at no cost with product registration

See complete warranty for details



Installation Notes

- 15" cutout width sufficient if door protrudes beyond adjacent cabinetry
- No additional clearance is needed for ventilation
- Do not obstruct front grille air flow









