FRIGIDAIRE GALLERY

Built-In Cooktops

FGGC3047Q S/W/B



Signature Features



Power BurnerPower Burner offers more power and faster boil time.



Continuous Corner-To-Corner Grates

Continuous grates make it easy to move heavy pots and pans between burners without lifting.



Express-Select® Controls
Easily go from warm to boil.



Approved Over Frigidaire® Electric Wall Ovens

Cooktops are approved for installation above any of our Single Electric Wall Ovens.

30" Gas

Product Dimensions

 Width
 30"

 Depth
 21-3/4"

 Height
 4-1/4"

More Easy-To-Use Features

Low Simmer Burner

Perfect for delicate foods and sauces.

Electronic Pilotless Ignition

LP Gas Conversion Option

A.D.A. Compliant

When properly installed, this model is A.D.A.-qualified based on the United States Access Board's A.D.A./A.B.A. Accessibility Guidelines and the Department of Justice's 2010 A.D.A. Standards for Accessible Design.

Available in:



Burners	BTU
Right Front	12,000
Right Rear	5,000
Left Front	9,500
Left Rear	7,500
Center	750 - 18,000




FGGC3047Q S/W/B 30" Gas

FF	R 1	G۱	D		IR	RΕ
G	Α	L	L	Ε	R	Y.

Features			
Controls	Express-Select®		
Surface Type	Stainless Steel Recessed (S), Color-Coordinated Recessed (W/B)		
Sealed Gas Burners	Yes		
Grates	Continuous Corner-To- Corner Cast Iron w/Black Matte Finish		
Right Front Burner (BTU)	12,000		
Right Rear Burner (BTU)	5,000		
Left Front Burner (BTU)	9,500		
Left Rear Burner (BTU)	7,500		
Center Burner	750 - 18,000		
Control Location	Front		
Knob Color	Stainless (S), Color-Coordinated (W/B)		
Knob Type	Cast Metal (S), Plastic (W/B)		
Certifications			
A.D.A. Compliant ¹	Yes		
Specifications			
Power Supply Connection Location	Right Rear		
Gas Supply Connection Location	Right Rear		
LP Gas Conversion Kit	Included		
Voltage Rating	120V/60Hz/15A		
Amps @ 120 Volts	1.0		
Minimum Circuit Required (Amps)	15		
Approved for Electric Single Wall Oven Combination Installation ²	Yes		
Shipping Weight (Approx.)	55 Lbs.		

When properly installed, this model is A.D.A.-qualified based on the United States Access Board's A.D.A./A.B.A. Accessibility Guidelines and the Department of Justice's 2010 A.D.A. Standards for Accessible Design. ²Cooktops are approved for installation above any of our Electric Single Wall Ovens.



NOTE: For planning purposes only, Always consult local and national electric and gas codes. Refer to Product Installation Guide for detailed installation instructions on the web at frigidaire.com.






Product Dimensions		Cutout I
A - Width	30"	Width (M
B-Depth	21-3/4"	Depth (M
C-Height	4-1/4"	Height

Cutout Dimensions	
Width (Min.)/(Max.)	28-1/4"/28-5/8"
Depth (Min.)/(Max.)	19-3/8"/19-3/4"
Height	8"

Granite Countertop Installation Kit available.

Accessories information available on the web at frigidaire.com





	Required Clearances					
A - Width	B - Depth	C - Height	G (min.)	H (min.)	I (min.)	J (min.)
30"	21-3/4"	4-1/4"	2"	12"	12"	2-1/4"
Product Cutout Dimensions			K - Cabinet Opening	L - For Unprotected	Utility Connection Locations	
D - Width (min max.)	E - Depth (min max.)	F-Height (min.)*	Width (min.)	Cabinet (min.)	Power Supply	Gas Supply
28-1/4" - 28-5/8"	19-3/8" - 19-3/4"	8"	30"	34"	Right Rear	Right Rear

Built-In Cooktop Specifications

- Product Shipping Weight (approx.) 55 Lbs.
- Voltage Rating 120V/60 Hz/15 Amps
- For use on adequately wired 120V, dedicated circuit having 2-wire service with a separate ground wire. Appliance must be grounded for safe operation.
- Amps @ 120 Volts = 1.0 Amps
- · Always consult local and national electric and gas codes.
- Cooktop cutout height includes clearance needed beneath cooktop to allow for gas supply connection. Recommended location for grounded 120V outlet is on rear wall in an 8"-wide by 10"-high area, positioned 22" above floor surface and 4" from right side of cooktop centerline. Access to underside of cooktop and junction box must be provided for inspection and service.
- · Cooktop ships with 3/4" factory regulator.
- LP Gas conversion kit supplied.
- Overhead cabinetry should not exceed a 13" maximum depth.
- · Absolute minimum horizontal distance between overhead cabinets installed to either side of appliance must be no less than 30'
- · Allow 34" minimum clearance between top of cooktop platform and bottom of unprotected wood or metal overhead cabinet.

USA • 10200 David Taylor Drive • Charlotte, NC 28262 • 1-800-FRIGIDAIRE • frigidaire.com

- Allow 2" minimum distance between rear edge of cutout and adjacent combustible surface (or backsplash)
- · Allow 12" minimum required clearance from left edge of cooktop to adjacent combustible surface and 12" minimum from right edge of cooktop to adjacent combustible surface.
- Installation of drawer beneath cooktop requires 6-1/2" minimum clearance beneath countertop surface, and assured clearance for gas and electrical connections.
- To reduce risk of fire when using overhead cabinetry, install range hood that projects horizontally a recommended minimum of 5" beyond bottom of cabinets.
- Gas Built-In Cooktop model FGGC3047Q is approved to be used over any Frigidaire® Electric Single Wall Oven. (Refer to Gas Cooktop Installation Over 30"/27" Electric Single Wall Oven Specifications page on web.)

Note: For planning purposes only. Refer to Product Installation Guide on the web at frigidaire.com for detailed instructions.

Optional Accessories

• Granite Countertop Installation Kit - (PN # 903103-9010).



subject to change

Œ