



# INSTALLATION AND USER INSTRUCTIONS FOR THE GAS RANGE TOP FOR THE HOME

THIS APPLIANCE WAS DESIGNED FOR EASE OF INSTALLATION AND OPERATION. HOWEVER, WE RECOMMEND THAT YOU READ ALL SECTIONS OF THIS MANUAL BEFORE YOU BEGIN INSTALLATION. INSTALLATION IS TO BE PERFORMED BY AN APPROVED GAS INSTALLATION OR GAS SERVICE TECHNICIAN. **IN THE COMMONWEALTH OF MASSACHUSETTS A LICENSED PLUMBER OR GAS FITTER** CAPABLE OF REVIEWING AND PERFORMING THE MANUFACTURER'S INSTALLATION CHECKLIST SHOULD INSTALL THIS APPLIANCE. THE INSTALLATION CHECKLIST IS INCLUDED AT THE REAR OF THIS BOOKLET.

DO NOT REMOVE PERMANENTLY AFFIXED LABELS, WARNINGS OR DATA PLATES FROM YOUR APPLIANCE. THIS MAY VOID THE MANUFACTURER'S WARRANTY AND/OR HINDER EFFECTIVE SERVICING AND MAINTENANCE.

THESE INSTRUCTIONS ARE TO REMAIN WITH THE APPLIANCE AND THE CONSUMER IS TO RETAIN THEM FOR FUTURE REFERENCE.

**WARNING:** If the information in this manual is not followed exactly, a fire or explosion may result causing property damage, personal injury or death.

Do not store or use gasoline or other flammable vapors and liquids in the vicinity of this or any other appliance.

#### **WHAT TO DO IF YOU SMELL GAS**

- Do not try to light any appliance
- Do not touch or activate any electrical switch
- Do not use any phone in your building
- Immediately call your gas supplier from a neighbor's house
- Follow the gas supplier's instructions
- If you cannot reach your gas supplier, call the fire department

**GAS-FIRED**





Since 1880, we have been dedicated to quality! We believe that our success can only be measured by the continuing success of our customers. We achieve customer satisfaction by ensuring that each of our employees understands, meets and exceeds customer expectations. We establish and maintain an environment that encourages all employees to pursue continuous improvement in quality and productivity.

Our quality policy is monitored by the highest levels of management.

We hope you enjoy your new appliance and we THANK YOU again for believing in our product as much as we do.

*The staff and team at Prizer Stove Works !*

## WELCOME

...to the exciting world of BlueStar™ cooking! You have purchased one of the finest appliances available for home use, which shows that you take cooking seriously. As the owner of a new BlueStar appliance you can look forward to years of cooking enjoyment. You will prepare meals with the speed and accuracy of a professional chef right in your own kitchen! All equipment is designed and manufactured to the highest quality standards in the industry specifically to meet the needs of the world's most demanding chefs: you. From simmering to sautéing, baking and broiling these versatile appliances provide the flexibility you need in any cooking application. Commercial styling adds a touch of elegance to your kitchen like no other appliance can. What's more, this high quality, high-performance appliance is backed by our professional service network from coast to coast to provide you with quick, competent technical service should the need arise. Please take a few moments now to fill in the information below for your future reference. In the event you require parts or service, this information will be needed to ensure you receive the highest quality service we can provide.

DATE OF PURCHASE

DEALER'S NAME

DEALER'S ADDRESS

DATE OF INSTALLATION

INSTALLER'S NAME

INSTALLER'S ADDRESS

MODEL NUMBER

SERIAL NUMBER

NOTE: WARRANTY SERVICE MUST BE PERFORMED BY AN AUTHORIZED SERVICE AGENT. YOU MAY REQUEST WARRANTY SERVICE BY CALLING 800-449-8691. YOU MAY ALSO REQUEST SERVICE VIA THE INTERNET BY SUBMITTING THE SERVICE REQUEST FORM AT [WWW.BLUESTARCOOKING.COM](http://WWW.BLUESTARCOOKING.COM)

**In the Commonwealth of Massachusetts, gas connections must be performed by a licensed plumber or licensed gas fitter.**

# TABLE OF CONTENTS

Introduction .....	2
Welcome.....	3
Table of Contents .....	4
Safety Instructions.....	5
Site Preparation .....	6
Dimensions and Specifications.....	7-30
Installation .....	31-34
Unpacking .....	31
Backguard .....	32
Gas Connections.....	33
Electrical Connections.....	34
Ventilation.....	34
Operation.....	35-37
Before You Turn It On .....	35
Burners .....	35
Griddle .....	35
Charbroiler .....	36
Raised Griddle Broiler .....	36
French Top .....	36
Cleaning .....	38-39
Body .....	38
Burners .....	38
Griddle Plates.....	38
Charbroiler .....	39
French Top .....	39
Helpful Hints.....	40
Care and Maintenance .....	41
Troubleshooting .....	42
Warranty.....	43-44
Performance Checklist .....	45-46

## SAFETY INSTRUCTIONS

To avoid personal injury or property damage, please read and follow these important safety precautions.

1. Before any maintenance or repairs are performed, disconnect the appliance from the electric supply.
2. Your appliance should be installed by a qualified gas installation technician. Have the technician show you the exact location of the gas shutoff valve on the incoming gas line so you know how to turn off the gas if necessary.
3. In the event of a power failure, do not attempt to operate the appliance or light any of the burners. This is a gas fired appliance that employs electrical components such as the ignition and safety devices.
4. Do not attempt to repair or replace any part of this appliance unless specifically instructed to do so by this manual. In-warranty service must be performed by an authorized service agency.
5. Do not store flammable materials on or near the appliance. Keep the appliance area clean and free of combustible materials, gasoline and other flammable vapors and liquids. A check before each use to determine that no hazardous materials are in the area is recommended.
6. The push-to-turn control knobs on this appliance are designed to be child-safe, however, not a guarantee of operation. Children should not be left alone or unattended in the kitchen while the appliance is in use.
7. This appliance should not be operated without a properly sized and operational ventilation hood.
8. The ventilation and flue ways of this appliance must remain unobstructed at all times.
9. Additional care should be exercised if your appliance is equipped with a high-shelf. During heavy or continued use this shelf may become hot. Do not place combustible materials or plastics on this shelf.
10. Do not store items of interest to children above the appliance. Children, as well as adults, should never be allowed to sit, stand, or climb on any part of the appliance. Serious injury may occur.
11. Never leave the appliance unattended during use. A boil-over may occur, causing spills which may ignite.
12. Do not use water on grease fires. Never pick up a flaming pan. It is recommended you purchase a multi-purpose dry chemical or foam-type fire extinguisher for your home. Store it in close proximity to your appliance.
13. If you are flaming liquor or other spirits, and your appliance is installed under a vent hood, **TURN THE FAN OFF**. The draft created could cause the flames to spread out of control.
14. For your safety, never use your appliance or any other cooking appliance as a space heater to warm or heat the room.
15. Use only dry potholders. Moist or damp potholders on hot surfaces may result in steam burns. Do not allow potholders to touch hot burner areas. Do not use a towel or other bulky material as a potholder.
16. To reduce the risk of burns, ignition of flammable materials, and spillage, the handle of any pot or pan should be positioned so that it does not extend over adjacent burners or the front of the appliance.


### WARNING

**Operation of this product could expose you to carbon monoxide if not adjusted properly. Inhalation of carbon monoxide is known to the state of California to cause birth defects or other reproductive harm.**



## SITE PREPARATION

- This appliance has been designed to be installed directly against rear walls and side base cabinets. It cannot be installed directly against tall side cabinets, side walls, tall appliances or base cabinets extending beyond 24 inches [610 mm].
- Side trims must be at least 11/16 inch [17.5 mm] above the adjoining counter top surfaces.
- Any openings in the back wall or the floor of the installation site must be sealed.
- Each gas appliance shall be located with respect to building construction and other equipment to permit access to the appliance. Such access and clearance is necessary for cleaning and servicing.
- Do not push against the edges or sides of any appliance in an attempt to slide it into position. Although all metal parts are deburred during the manufacturing process, serious injury could occur if the appliance were to move suddenly while being positioned. We recommend you use gloves during the installation process.
- For optimum performance the appliance should be leveled during installation. A carpenter type level should be placed on the unit three ways: side to side; front to back; diagonally.
- If the appliance is installed in an island or cabinet cut-out the edges should be shimmed with small metal coupons

# RGTNB24 RANGE TOP SITE PREPARATION




# RGTNB24 RANGE TOP SPECIFICATIONS



# RGTNB24 RANGE TOP SPECIFICATIONS


## CONFIGURATIONS





### SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ \_ 22,000 BTU
- CHAR GRILL BURNER RATING \_ \_ \_ \_ 30,000 BTU
- GRIDDLE BURNER RATING \_ \_ \_ \_ \_ 30,000 BTU
- FRENCH TOP BURNER RATING \_ \_ \_ \_ 18,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

# RGTNB30 SITE PREPARATION




# RGTNB30 RANGE TOP SPECIFICATIONS



- A - ISLAND TRIM HEIGHT - 9 3/8"
- B - 6" STANDARD BACKGUARD HEIGHT - 14-3/8"
- C - 17" BACKGUARD HEIGHT - 25-3/8"
- D - HIGH SHELF BACKGUARD HEIGHT - 32 1/8"

# RGTNB30 RANGE TOP SPECIFICATIONS


RGTNB304BSS





## SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ \_ 22,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

# RGTNB364BSS SITE PREPARATION




# RGTNB364 RANGE TOP SPECIFICATIONS



- A - ISLAND TRIM HEIGHT -  $9 \frac{3}{8}$ "
- B - 6" STANDARD BACKGUARD HEIGHT -  $14 - \frac{3}{8}$ "
- C - 17" BACKGUARD HEIGHT -  $25 - \frac{3}{8}$ "
- D - HIGH SHELF BACKGUARD HEIGHT -  $32 \frac{1}{8}$ "

# RGTNB364 RANGE TOP SPECIFICATIONS


## CONFIGURATIONS





### SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ 22,000 BTU
- CHAR GRILL BURNER RATING \_ \_ \_ 15,000 BTU
- GRIDDLE BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

# RGTNB488BSS SITE PREPARATION




# RGTNB48 RANGE TOP SPECIFICATIONS



# RGTNB48 RANGE TOP SPECIFICATIONS


## CONFIGURATIONS





### SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ 22,000 BTU
- 12" CHAR GRILL BURNER RATING \_ \_ 15,000 BTU
- 24" CHAR GRILL BURNER RATING \_ \_ 30,000 BTU
- 12" GRIDDLE BURNER RATING \_ \_ \_ 15,000 BTU
- 24" GRIDDLE BURNER RATING \_ \_ \_ 30,000 BTU
- FRENCH TOP BURNER RATING \_ \_ \_ 18,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
- OPERATING GAS PRESSURE \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL


# RGTNB6010BSS SITE PREPARATION



# RGTNB60 RANGE TOP SPECIFICATIONS




CONFIGURATIONS





SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ 22,000 BTU
- 12" CHAR GRILL BURNER RATING \_ \_ 15,000 BTU
- 24" CHAR GRILL BURNER RATING \_ \_ 30,000 BTU
- 12" GRIDDLE BURNER RATING \_ \_ \_ 15,000 BTU
- 24" GRIDDLE BURNER RATING \_ \_ \_ 30,000 BTU
- FRENCH TOP BURNER RATING \_ \_ \_ 18,000 BTU
  
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
  
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

# RGTNB364GHC SITE PREPARATION



# RGTNB364GHC RANGE TOP SPECIFICATIONS



LOCATION OF ELECTRICAL CONNECTION →  $1 \frac{1}{16}$ "

NOTE: A HOLE MUST BE DRILLED INTO THE BASE CABINET TO ACCEPT ELECTRICAL CORD.

LOCATION OF GAS LINE →  $2$ "

NOTE: A HOLE MUST BE DRILLED INTO THE BASE CABINET TO ACCEPT GAS LINE.


A {  $17$ " BACKGUARD HEIGHT -  $25 \frac{3}{8}$ "

      HIGH SHELF BACKGUARD HEIGHT -  $32 \frac{5}{8}$ "

      HIGH BACKGUARD HEIGHT -  $32 \frac{5}{8}$ "

# RGTNB364GHC RANGE TOP SPECIFICATIONS


## CONFIGURATIONS





### SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ 22,000 BTU
- GRIDDLE/BROILER BURNER RATING \_ 15,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

# RGTNB486GHC SITE PREPARATION




# RGTNB486GHC RANGE TOP SPECIFICATIONS



- A {  $17$ " BACKGUARD HEIGHT -  $25 \frac{3}{8}$ "  
 HIGH SHELF BACKGUARD HEIGHT -  $32 \frac{5}{8}$ "  
 HIGH BACKGUARD HEIGHT -  $32 \frac{5}{8}$ "

# RGTNB486GHC RANGE TOP SPECIFICATIONS


## CONFIGURATIONS





## SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ 22,000 BTU
- GRIDDLE/BROILER BURNER RATING \_ 15,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
  
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

# RGTNB606GHC SITE PREPARATION



# RGTNB606GHC RANGE TOP SPECIFICATIONS




A {
 

- 17" BACKGUARD HEIGHT -  $25 - \frac{3}{8}$ "
- HIGH SHELF BACKGUARD HEIGHT -  $32 \frac{5}{8}$ "
- HIGH BACKGUARD HEIGHT -  $32 \frac{5}{8}$ "

# RGTNB606GHC RANGE TOP SPECIFICATIONS

## CONFIGURATIONS



### SPECIFICATIONS:

- SIMMER BURNER RATING \_ \_ \_ \_ \_ 9,000 BTU, 130°F
- TOP BURNER RATING \_ \_ \_ \_ \_ 15,000 BTU
- TOP POWER BURNER RATING \_ \_ \_ 22,000 BTU
- GRIDDLE/BROILER BURNER RATING \_ 15,000 BTU
- ELECTRICAL REQUIREMENTS \_ \_ \_ \_ 120V, 60Hz, 15 AMPS, 1 PH  
(UNIT MUST BE ON A NON-GFI, DEDICATED OUTLET)
- OPERATING GAS PRESSURE \_ \_ \_ \_ NAT: 5.0" WC  
LP: 10.0" WC
- INSTALLATION CLEARANCE \_ \_ \_ \_ 0" SIDE CABINET  
0" BACK WALL

## INSTALLATION

### UNPACKING

1. Check the package for damage. If any damage is visible you should mark the bill of lading you sign that there may be concealed damage.
2. Insure the container is upright. If the container is not upright major damage can occur to your appliance. If damage is discovered, do not refuse delivery. Contact the dealer and file appropriate freight claims. Save all packaging material. Do not contact the manufacturer. Your appliance was shipped from the dealer you purchased it from. Shipping damage claims are to be resolved between the customer, shipping carrier and dealer. The manufacturer may assist in resolving any such claims, but such assistance does not relieve you of your responsibility.
3. Move the container as close to its installation location as possible. This will reduce moving and handling your appliance once it is out of its shipping container.
4. Cut the straps holding the carton to the palette. Lift the unit directly out of the box. Do not use a hammer. Do not cut the carton with a razor, utility or box cutting knife.
5. Thoroughly inspect your appliance for damage. If damage is discovered, do not refuse delivery. Contact the dealer and file appropriate freight claims. Save all packaging material. Do not contact the manufacturer. Your appliance was shipped from the dealer you purchased it from. Shipping damage claims are to be resolved between the customer, shipping carrier and dealer. The manufacturer may assist in resolving any such claims, but such assistance does not relieve you of your responsibility.
6. Remove and unpack any accessories shipped with your appliance. Make sure no hardware or accessories are left to be disposed of unintentionally.

**THIS PRODUCT IS A PROFESSIONAL PRODUCT AND REQUIRES A LICENSED PLUMBER, CERTIFIED GAS TECHNICIAN OR APPLIANCE INSTALLER. SELF INSTALLATION MAY VOID YOUR WARRANTY.**

## INSTALLATION

### BACKGUARD

All range tops require a backguard. Most models have the option of using: an island trim; 7 inch standard; 17 inch hi-back; 21 inch high shelf. Heritage Classic models require a 21 inch high shelf for all installations.


If you are using an island trim a six inch clearance between the back of the range and a combustible surface is required. If an island trim is to be used without this six inch clearance the back wall must be non-combustible *and* heat resistant material that extends below the top surface of the range a minimum of six inches.

All backguards follow the same basic installation. Using hardware supplied, align the backguard with the wrap around on each side

and slip the tongue into place. A minimum of six sheet metal screws (more depending on width) are to be installed, three on each end and more along the bottom edge.

Remove the two rear ring grate/top grates from the cooktop surface. Four sheet metal screws to be installed - down - into the cooktop support. Two screws are installed on each end ring grate/top grate position. Replace the removed grates.

If you are installing a high shelf there is an additional channel to be installed on each side first. The back guard then slips over this channel as you put it into position. This channel provides extra support for the higher rise of the 21 inch back.



## INSTALLATION

### GAS CONNECTIONS

1. The installation of this appliance must conform with all applicable local codes. In the absence of local codes, the installation must conform to the latest level of the National Fuel Gas Code, ANSI Z223.1/NFPA 54. In Canada, the installation must be in accordance with the current CAN/CGA B149.1 and B149.2.
2. This appliance can be configured to work with either natural gas or LP gas. Verify that the appliance and the incoming gas supply are compatible. Check the rating plate.
3. The gas supply line must be the same size or larger than the gas inlet of the appliance. Your appliance has either a ½" NPT or ¾" NPT gas inlet connection. We recommend the supply line be ¼" NPT larger than the gas inlet of the appliance.
4. Sealant used on pipe joints must be resistant to LP gas.
5. An installer provided manual shut-off valve must be installed in the gas supply line ahead of the appliance. This shut-off must be easily accessible in case of emergency.
6. All gas cooking equipment must have a pressure regulator on the incoming service line for safe and efficient operation. This appliance is equipped with such a gas pressure regulator. Incoming gas pressure should be checked with a manometer. The correct manifold pressure for natural gas is 5.0" wc. For LP gas the correct manifold pressure is 10" wc.
7. Incoming line pressure upstream of the appliance should be 1.0" wc greater than the operating manifold pressure. Service pressure may fluctuate for a variety of reasons. Under no circumstances should the factory installed regulator be removed or by-passed.
8. The factory installed pressure regulator will withstand an input pressure of ½ PSI (12" wc). If the incoming pressure exceeds the maximum rating a step-down regulator is required.
9. The appliance and its individual shut-off valve must be disconnected from the gas supply line during any pressure testing in excess of ½ PSI [3.5 kPa].
10. The appliance must be disconnected from the gas supply by closing its individual shut-off during any pressure testing less than ½ PSI [3.5 kPa].
11. Check to see that all installer supplied pipes and fittings are clear of debris, threading chips or other foreign particles before connecting the appliance to the supply line. Such particles will clog orifices and/or valves when pressure is applied. **Service to clean such clogs is not covered by your warranty.**
12. The incoming gas supply is brought from the inlet pipe. This is the only connection required via the installer-supplied shut-off valve.
13. If the appliance is to be installed with flexible couplings and/or a "quick disconnect" the installer must use a commercially approved AGA Design certified flexible connector at least ½" NPT that complies with ANSI Z21.41. In Canada the connector must comply with CAN 16.10-88 and the "quick disconnect" device must comply with CAN 16.19M-79 and installed with a strain relief device.
14. Before putting the appliance into service test all gas connections for leaks. Use a soapy solution. **DO NOT USE AN OPEN FLAME TO CHECK FOR LEAKS.** Such a procedure is dangerous and it may not detect all the small leaks that a soapy solution will.
15. Air shutter adjustments are preset at the

## INSTALLATION

factory. These adjustments may need to be redone and/or fine tuned by the installer. These adjustments are normal. **They are the responsibility of the qualified installer and are not covered by your warranty.**

16. A gas conversion performed in the field may void your warranty. Contact your dealer for information regarding the conversion from one type of gas supply to another.

### ELECTRICAL CONNECTIONS

1. The installation of this appliance must conform with all applicable local codes. In the absence of local codes, the installation must conform to the latest level of the National Electric Code, ANSI/NFPA 70.
2. This appliance is equipped with a standard three prong polarized, NEMA 5-15P line cord to be plugged into a 120Volt 15 Amp outlet.
3. Removing the grounding prong from the plug will void the manufacturer's warranty.
4. The cord exits the appliance at the lower rear toward the right (viewed from front) side.
5. If the electrical supply is not turned on or is interrupted the appliance will not operate.
6. The circuit where you plug your appliance must be grounded and polarized.
7. We recommend the circuit for your appliance be a non-GCFI dedicated line.
8. It is recommended that your circuit never include a microwave oven.

**This appliance is equipped with a three-pronged grounding plug for your protection against shock hazard and should be plugged directly into a properly grounded receptacle. Do NOT cut or remove the grounding prong from this plug.**

**If the appliance is not grounded or its polarity is reversed severe shock hazards can exist.**

### VENTILATION

Proper ventilation is highly important for good operation. This appliance must be installed under a properly designed canopy hood. The hood should be six inches [150 mm] wider than the appliance.

A strong exhaust fan can create a vacuum in the room. For proper air balance work with your dealer and/or contactor to properly size your hood and its exhaust fan. It is recommended that your exhaust hood be powerful enough to move a minimum of 300 cfm.

### IMPORTANT

**ALL GAS BURNERS NEED SUFFICIENT AIR TO OPERATE AND LARGE OBJECTS SHOULD NOT BE PLACED IN FRONT OF THIS APPLIANCE WHICH WOULD OBSTRUCT THE AIR FLOW THROUGH THE FRONT. OBJECTS SHOULD NOT BE PLACED ON THE REAR BACKGUARD WHILE IN USE. THIS COULD OBSTRUCT THE VENTING SYSTEM OF THE OVEN'S FLUE PRODUCTS.**

### WARNING

## OPERATION

### BEFORE YOU TURN IT ON....

- As part of the installation protective plastic wrappers on stainless steel surfaces should be removed. These wrappers must be removed before operation.
- New appliances are wiped clean with various cleaners and solvents to remove visible signs of dirt, oil and grease before leaving the factory. After installation, performance checks and adjustments, the appliance should be allowed to heat to burn off any such oils from internal parts. The presence of such coatings is normal as part of the manufacturing process. The ventilation hood should be turned on and the area well ventilated to allow fumes to escape safely.
- Removable parts should be washed with hot soapy water, well rinsed and wiped dry.
- Complete and mail your Performance Checklist to validate your warranty.

### BURNERS

- Remove the top grates and thoroughly wash them with hot soapy water, rinse and wipe dry. Extended exposure to moisture may cause these cast parts to rust.
- To light a burner turn the corresponding control knob to HIGH.
- This knob is a gas control valve and an electric switch. Turning to the High position begins the ignition sequence.
- The igniters begin to “click”. As gas flows through the piping to the burner the sparking ignites it. After the flame lights the igniter senses its heat and the “clicking” automatically stops.
- ALL burners light at the HIGH setting.
- Burners are equipped with a re-ignite feature in case the flame is extinguished for any reason.
- At the High setting, flames should be

sharp with blue tips. Some yellow may appear depending on the type of gas being burned.

- Turn the flame lower so it does not wrap around the bottom edge of the pan.
- Burners may be operated at any knob position between LOW and HIGH.
- Never operate the burner with the knob between the HIGH and OFF position. If the flame goes out it will not re-ignite and gas leaks could occur.
- When you turn the valve off the flame may linger several seconds until all the gas in the feeder tube is burned up.
- Turn off the burner from a low setting to avoid popping of the burner.

**NEVER use this appliance as a space heater to heat or warm the room. Doing so may result in carbon monoxide poisoning and overheating of the oven.**

- Place a pot or pan on top of the burner before turning on the burner for ideal ignition

### GRIDDLES

- New griddles must be seasoned prior to their first use.
- Remove all factory materials and wash the griddle plate with hot soapy water. Rinse and dry thoroughly.
- Apply a light coating of unsalted peanut oil to the top, sides and front of the griddle plate. Wipe away any excess oil.
- To light the burner turn the knob counter clockwise to the medium setting.
- When the griddle is lit turn the heat setting back to “LOW”.
- After a short while as the griddle heats it likely will discolor with the heat. Colors range through different shades of blue and black. This is a normal characteristic of

## OPERATION

- griddle plates and should be expected.
- After approximately 30 minutes, wipe away the oil and apply a second coat. Wipe away the excess.
- Increase the heat setting at the control knob 1/8 turn every 15 minutes. Stop at three quarters of the available knob rotation. Do NOT heat to the maximum setting during the seasoning process.
- During normal use if the griddle is not overheated or food is not allowed to stick re-seasoning should not be required.
- If necessary the seasoning procedure may be repeated.
- Always pre-heat the griddle at least 10 minutes before cooking. Pre-heat on low. Do NOT pre-heat on high.
- Do not bang the griddle plate with metal cooking utensils. Be careful not to gouge the griddle plate surface.
- Do NOT overheat the griddle. In between loads turn to a lower setting. Turn off when not in use.
- Allow to cool when done cooking. Scrape off excess food and wipe off oil coatings. Do NOT wash griddle plate or it will require re-seasoning. Apply a new oil coating and wipe off excess. Do NOT allow to stand without a new oil coating to prevent rust.
- Never flood a hot griddle with cold water. This may cause the griddle plate to crack or warp and will void your warranty.

### CHARBROILER

- Insure there is nothing on the grilling rack.
- Push in and turn the control knob counter clockwise approximately halfway to “HIGH”.
- The hot surface igniter will glow brightly, gas will flow from the valve and the burner will light. This takes approxi-

mately one minute.

- Adjust the flame to the desired height.
- After cooking allow to cool completely.
- Remove the drip pan slowly, discard grease and food particles. Wash with warm soapy water, rinse and replace.
- The char broiler grate is porcelain coated and may be washed with hot soapy water and a grill brush.

### RAISED GRIDDLE CHARBROILER

- The raised griddle broiler section has three elevations. Combine the various rack positions and burner settings for different foods and different finished results.
- Position rack to the proper height for the food to be cooked.
- Press in and turn burner knob approximately halfway to “HIGH”. The spark igniter will begin to “click”, gas will flow and the burner will light.
- The spark igniter will click until the griddle is lit. If the igniter clicks more than 10 times turn the valve off, wait five minutes and try again.
- Adjust the valve to get the setting you desire.
- After cooking allow griddle and racks to cool completely.
- The pull out racks under the raised griddle may be cleaned with hot soapy water.
- In the event heavy soiling occurs a commercial oven cleaner may be used.

### FRENCH TOP

- Remove all factory materials and wash the French Top plate with hot soapy water. Rinse and dry thoroughly.
- To light the burner turn the corresponding control knob to HIGH. This knob is a gas control valve and an electrical switch. Turning to the High position begins the ignition sequence. The igniters begin to

## OPERATION

“click”. As gas flows through the piping to the burner the sparking ignites it. After the flame lights the igniter senses its heat and the clicking automatically stops.

- After a short while as the French Top heats it will begin to discolor. This is a normal characteristic of steel plates and should be expected. The coloring will be varying shades of blue to black. It is permanent and to be expected.
- Always pre-heat your French Top at least 10 minutes before cooking. After lighting turn the flame to Low. Pre-heat on Low. Do not pre-heat on High.
- Do not bang the plate with metal cooking utensils. Be careful not to gouge the surface.
- In between uses turn the control to a lower setting. Turn off when not in use.
- Your French Top is not a cooking griddle. It is not intended for food to contact or be cooked directly on the steel plate.
- You may wish to remove one or both center rings to insert a wok directly over the burner flame for stir-fry cooking.
- Allow to cool when done cooking.
- Never flood a hot steel plate with cold water. This may cause the steel to crack or warp and will void your warranty.

## CLEANING

### BODY

- All stainless steel and painted parts should be cleaned regularly with hot soapy water.
- Commercially available stainless steel cleaners may be used on stainless steel. Be sure to follow manufacturer's instruction for use.
- Do NOT use steel wool or metal pads or other abrasive cleaners. These surfaces are painted or polished and using these products will scratch and damage your finish.
- In extreme conditions use a cloth soaked in hot water to sit on the soiled area to soften the residue and allow it to be safely cleaned off. LIGHT scraping with a rubber or nylon spatula may be used to finish lifting residue off.
- Do NOT use a metal knife, spatula or similar or any metal tool to scrape these surfaces.
- Do NOT permit citrus or tomato juices to sit and dry on these surfaces. Wipe such spills immediately. Citric acid will discolor stainless steel.

### BURNERS

- The top grates of your appliance may be effectively cleaned with hot soapy water.
- In the event of heavy soiling, a commercially available oven cleaner may be safely used on these parts. Be sure to follow the manufacturer's instructions for use. Insure the cleaning chemical does not contact any painted surfaces on your appliance.
- To insure proper fit and safe use replace the top grates to their proper position.

### GRIDDLE PLATES

- Always allow the griddle to cool before trying to clean it.

- Remove the drip pan by pulling straight toward you - SLOWLY.
- Beware to avoid spilling the pan. Clean with hot soapy water.
- The grease tube may be cleaned with hot soapy water and a bottle brush.
- Clean the drip pan and grease tube thoroughly after each use to avoid a fire hazard.
- Apply a small amount of peanut oil to the griddle plate. Rub vigorously with a small patch of burlap or other rough cloth to remove food particles and residue.
- Stubborn dirt and food build-up may be cleaned with a nylon pad coated with a thin layer of cooking oil.
- Commercially available griddle cleaners may be used. Be sure to follow the manufacturer's instructions for use. After use, rinse TWICE - once with vinegar and water, then with plain water.
- If Griddle is heavily soiled, pour club soda slowly onto the griddle. The griddle should still be slightly warm and the soda should be room temperature--not cold. Use a spatula to push debris toward the grease trap.
- Insure the cleaning chemical does not come in contact with any painted surfaces on your appliance.
- Re-season the griddle surface immediately. It is a steel plate that will rust if not seasoned.
- Do NOT use soap on your griddle surface.
- Do NOT pour cold water on a hot griddle surface. It will cause it to warp and/or crack and will void your warranty.
- In the event of extreme conditions a fine grain griddle stone may be required. Contact your dealer for information.

### CHARBROILER

## CLEANING

- Always allow the char broiler to cool before trying to clean it.
- Remove the drip pan by pulling straight toward you - SLOWLY.
- Beware to avoid spilling the pan. Clean with hot soapy water.
- The grease tube may be cleaned with hot soapy water and a bottle brush.
- Clean the drip pan and grease tube thoroughly after each use to avoid a fire hazard.
- The char broiler grates are porcelain coated or chrome plated. They may be cleaned with hot soapy water.
- In the event of extreme conditions commercially available oven cleaners may be used to clean these parts. Be sure to follow the manufacturer's instructions for use.
- Insure the cleaning chemical does not come in contact with any painted surfaces on your appliance.

### FRENCH TOP

- Your French Top needs to be cleaned regularly along with the top of your range. Occasionally between cleanings small rust spots may begin to appear. This may not happen, it is dependent on many variables. If cleaned promptly they should be removable with a nylon scouring pad.
- Stubborn dirt build-up may be cleaned with a nylon pad coated with a thin layer of cooking oil.
- Commercially available griddle cleaners may be used. Be sure to follow the manufacturer's instructions for use. After use, rinse TWICE – once with vinegar and water, then with plain water. Insure the cleaning chemical does not come in contact with any painted surfaces on your appliance.

## HELPFUL HINTS

### TOP BURNERS

- Insure the top grates are properly positioned so your cooking pan will sit flat and level.
- A front top grate may be removed and the cooking pan placed directly into the cut-out for stir-fry cooking.

Suggested Griddle Settings	
Eggs	Low
Pancakes	Medium High
Hamburgers or Steaks (rare)	High
Hamburgers or Steaks (medium)	Medium High
Grilled Sandwiches	Medium

Suggested Raised Broiler Settings				
What	How	Where	Temp	Time
Steak	Rare	Top Rack	High	6-8 minutes/side
	Medium	Middle Rack	High	8-10 minutes/side
Hamburger	Medium	Top Rack	High	6-8 minutes/side
	Medium-Well	Middle Rack	High	8-10 minutes/side
Fish	1" thick	Middle Rack	Medium-High	10-15 minutes
	1/2 " Thick	Top Rack	Medium-High	8-10 minutes
Chicken	Boneless Breast	Middle Rack	Medium	15 minutes/side
	Leg & Thigh	Lower Rack	Medium	25 minutes/side
Garlic Bread		Lower Rack	Medium	3-5 minutes

## CARE AND MAINTENANCE

### AIR SHUTTER ADJUSTMENTS

Air shutter adjustments are preset at the factory. These adjustments may need to be redone and/or fine tuned by the installer. These adjustments are normal. They are the responsibility of the qualified installer and are not covered by your warranty.

### TOP BURNER AIR SHUTTER ADJUSTMENT


Before attempting to adjust any top burner air shutter, insure the following has been checked and is correct:

- Proper gas type - match serial plate
- Proper regulator setting
- Orifice aligned - parallel with the venturi to the burner

After verifying the gas, regulator and orifices adjust the air shutter by:

- Remove all top cooking sections associated with the burner(s) to be adjusted.
- Use a screwdriver to loosen the air shutter tightening screw.
- Turn the air shutter as required to adjust the flame - open gap for "lazy" flame, close gap for "lifting" flame.
- Test burner.
- If necessary, turn off burner and readjust.
- Turn off burner, tighten shutter screw and replace top sections when complete.

A properly adjusted burner will have a conical shaped blue flame, however, on some larger burners (22K) the cones are close together and blend into one another. Yellow tips normally flicker occasionally with natural gas, more often with propane. The flame should be almost all blue all the time.



### TOP BURNER LOW FLAME ADJUSTMENT

1. Insure gas pressure regulator is set properly. This setting is typically checked and adjusted by a service agent using a manometer.
2. Turn the burner on low.
3. Remove the burner knob from the valve stem by pulling straight toward you.
4. Insert a small slotted screwdriver blade into the "D" shaped valve stem inserting it into the adjusting screw.
5. Turn the adjusting screw 1/8 of a turn at a time - clockwise to lower the flame, counter-clockwise to raise the flame.
6. Replace knob by aligning the "D" shaped cut-out and pressing straight onto the valve stem

## TROUBLESHOOTING

PROBLEM	SOLUTION
Burner won't light—no “clicking” from igniter	Ensure appliance is plugged in. Ensure circuit is not tripped or fuse blown.
Burner won't light—”clicking”, no flame	Ensure gas is turned on. Ensure burner ports are clean. Try a second burner for same or different result. Ensure electrode is plugged in. Ensure electrode is properly lined up. Ensure electrode is not cracked—spark not in correct place. Ensure venture tube is properly on orifice after cleaning.
Burner lights, “clicking” won't stop	Ensure electrode wires are properly connected after cleaning. Call for service.
LAZY flame—floating, larger in size than normal	Air shutter adjustment.
LIFTING flame—well defined with visible inner core, noisy, gap between burner and flame	Air shutter adjustment.

# WARRANTY

**WHAT IS COVERED?** Prizer-Painter provides the following limited warranties to the original retail purchasers of Products sold and installed in the continental United States and Canada on or after February 22, 2002:

**Initial Seven (7) Day Limited Warranty.** Prizer-Painter warrants that all cosmetic components of its Products will, under normal use and service, be free from defects in materials and workmanship for a period of seven (7) calendar days from the date of delivery (the "Warranty Period") to the original retail purchaser. For purposes of this Limited Warranty, cosmetic components include top grates, ring grates, plate rail, kick panel, body sides, glass, control panel, door panel, back guards, oven seals, light bulbs, and enameled parts. All warranty claims for cosmetic items must be reported immediately within seven calendar days of delivery or such claims will not be honored. Floor models and demonstration units are not covered under the 7 Day Limited Warranty. Please refer to your installation checklist to activate your limited warranty.

**One (1) Year Limited Warranty.** Prizer-Painter warrants that all functional components (except cast iron burner tops) of its Products will, under normal use and service, be free from defects in materials and workmanship for a period of one (1) year from the date of delivery (the "Warranty Period") to the original retail purchaser. For purposes of this Limited Warranty, functional components include all components of the Product other than the cosmetic components covered by the initial seven day limited warranty and the cast iron burner tops covered by the 10 year limited warranty. Floor models are not covered under the One (1) Year limited Warranty but are covered by a ninety (90) day labor and a One (1) Year Limited Parts Warranty with proof of date of install and a completed Installation Checklist. Demonstration units are not covered under the One (1) Year Limited Warranty. Please refer to your installation checklist to activate your limited warranty. **Failure to send a complete and accurate copy of the installation checklist within 15 days of installation will invalidate your limited warranty.**

**Ten (10) Year Limited Warranty.** Prizer-Painter warrants that all functional components of its cast iron burner tops will, under normal use and service, be free from defects in materials and workmanship for a period of ten (10) years from the date of delivery (the "Warranty Period") to the original retail purchaser. Please refer to your installation checklist to activate your limited warranty. **Failure to send a complete and accurate copy of the installation checklist within 15 days of installation will invalidate your limited warranty.**

If any Product fails to comply with the foregoing Limited Warranties during the applicable Warranty Period, Prizer-Painter will, at its option, either (i) pay the reasonable labor and material costs to have the Product repaired by a factory authorized service agent; (ii) replace the Product or defective component of the Product; or (iii) if in Prizer-Painter's sole judgment circumstances are such as to preclude the remedying of any breach of warranty by repair or replacement, then Prizer-Painter will refund the purchase price paid by the original purchaser. All repairs or replacement service must be performed by a factory authorized service agent. Additionally, all Products must be accessible for service in the home and must be accessible via public highways within 100 miles roundtrip of a factory authorized service agent. The purchaser will be responsible for the cost of additional mileage, non-standard service and special equipment to remove the Product for service so that there is accessibility on all sides of the Product. The repair or replacement of the Product or the return of the purchase price will be the purchaser's sole and exclusive remedy for any breach of this Limited Warranty or any other claim with respect to the Product, including those claims based on contract, warranty, or tort. In no event will Prizer-Painter's liability for any defective Product exceed the purchase price thereof. This exclusive remedy will not be deemed to have failed of its essential purpose so long as Prizer-Painter is willing and able to repair and/or replace defective Products in the manner prescribed herein or to provide a refund if, in Prizer-Painter's sole judgment, repair or replacement is not feasible or appropriate under the circumstances.

# WARRANTY

## **WHAT IS NOT COVERED?**

This Limited Warranty is the sole and exclusive warranty provided for the Product and extends only to original retail purchasers in the continental United States and Canada. This Limited Warranty is not transferable to any subsequent purchasers or users. If any implied warranties arise under any applicable law (including, but not limited to, implied warranties of merchantability and fitness for particular purpose), then the duration of those implied warranties will last only as long as the express warranties stated above. **Prizer-Painter will not under any circumstances be liable for any special, indirect, incidental or consequential damages of any kind, including but not limited to loss of business or profits, loss of use, or installation or removal costs.** Nor will Prizer-Painter be responsible for any shipping costs related to the repair or replacement of any Product under this Limited Warranty. Some States do not allow the exclusion or limitation of incidental or consequential damages or limitations on how long implied warranties last, so the above limitations may not apply to you.

This Limited Warranty does not apply to commercial usage or to any Products installed in any non-residential settings such as day cares, bed and breakfasts, hotels, nursing homes, churches, etc. This Limited Warranty also does not cover, and specifically excludes, chipping porcelain, porcelain igniters, calibrations and normal adjustments after installation and setup, normal care and maintenance, cleaning of parts, shipping damage, discoloration of the griddle, rust, gasket materials, ceramic materials, and fuses. Additionally, there is no warranty coverage for any Products that fail or have been damaged due to alterations or modifications; abuse; misuse; neglect; improper installation, instruction, handling, operation, maintenance or storage; accidental or intentional damage; normal wear and tear; unauthorized service or repairs, including unauthorized adjustments or calibrations performed on the Product; damage from natural disasters, fires, floods, earthquakes or other acts of God; loss of electrical power to the Product for any reason; alteration for outdoor use; damage due to the use of harsh chemicals (e.g., cleaning products improperly applied); or any other circumstances beyond Prizer-Painter's control. This Limited Warranty is also invalid if the original factory installed serial number has been altered or removed from the Product. The Purchaser is responsible for proper installation and normal care and maintenance of the Product. This warranty gives you specific legal rights, and you may also have other rights which vary from State to State.

## **OBTAINING WARRANTY SERVICE**

All warranty claims must be reported to Prizer-Painter Stove Works, Inc., 600 Arlington St., Reading, Pennsylvania 19611 prior to the expiration of the applicable Warranty Period. If a warranty claim relates to cosmetic parts, any such claim must be reported to Prizer-Painter within seven (7) calendar days after the Product has been delivered. The purchaser must call the factory at the toll free 1-800-449-8691 to re-port a warranty claim or to obtain information about warranty service. If any warranty claim is not submit-ted as required by this Limited Warranty, any such claim will be invalid and will not be honored. At the time the warranty claim is made, the purchaser must provide the model number of the Product, the serial number of the Product, proof of delivery, a description of the claimed defect, and proof of purchase of the Product, including the original retail receipt or invoice to establish the Warranty Period. Prizer-Painter must also be given an opportunity to inspect any defective Product.

All warranty repairs must be performed by a factory authorized service agent. Service will be provided during normal business hours. The purchaser will be responsible for any labor performed at over-time or premium rates. The purchaser is also responsible for making the Product accessible for service.

# PERFORMANCE CHECKLIST

This checklist has been developed to assure proper installation of your appliance  
 To validate your warranty you must mail or fax this form and a copy of your receipt to:  
 Warranty Department, Prizer-Painter, 600 Arlington Street, Reading, PA 19611, Fax (610) 376-2596

Customer Information (Please Print)

Product Information (Please Print)

Name: \_\_\_\_\_ Model No: \_\_\_\_\_  
 Address: \_\_\_\_\_ Serial No: \_\_\_\_\_  
 City: \_\_\_\_\_ Purchase Date: \_\_\_\_\_  
 State, Zip Code: \_\_\_\_\_ Installation Date: \_\_\_\_\_  
 e-mail: \_\_\_\_\_ Installer's Name: \_\_\_\_\_  
 Telephone: \_\_\_\_\_ Company: \_\_\_\_\_  
 Dealer: \_\_\_\_\_ Telephone: \_\_\_\_\_

CHECK ALL THAT APPLY
----------------------

Appearance and Aesthetics

- Exterior
- Top section
- Oven interior
- Broiler pan set

Electrical Connection

- Correct voltage
- Grounded outlet
- Polarized outlet
- No GFCI

Installation

- Proximity to cabinets
- Level
- Backguard in place
- Ventilation system
- Read User Manual
- Review safety instructions

Gas Connection

- Verify fuel—\_\_\_\_ Nat \_\_\_\_ LP
- Gas shut-off present and accessible
- Supply line properly sized
- Supply pressure checked
- Operating pressure checked
- All connections checked for leaks

Ignition

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Flame Adjustment

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Air/Gas Mixture

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Valve Operation

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Controls

- Burner knobs
- Thermostats
- Convection oven fan & switch
- Oven light switch

Oven Door

- Alignment
- Door seal
- Hinges

CUSTOMER COPY

# PERFORMANCE CHECKLIST

This checklist has been developed to assure proper installation of your appliance  
 To validate your warranty you must mail or fax this form and a copy of your receipt to:  
 Warranty Department, Prizer-Painter, 600 Arlington Street, Reading, PA 19611, Fax (610) 376-2596

Customer Information (Please Print)

Product Information (Please Print)

Name: \_\_\_\_\_ Model No: \_\_\_\_\_  
 Address: \_\_\_\_\_ Serial No: \_\_\_\_\_  
 City: \_\_\_\_\_ Purchase Date: \_\_\_\_\_  
 State, Zip Code: \_\_\_\_\_ Installation Date: \_\_\_\_\_  
 e-mail: \_\_\_\_\_ Installer's Name: \_\_\_\_\_  
 Telephone: \_\_\_\_\_ Company: \_\_\_\_\_  
 Dealer: \_\_\_\_\_ Telephone: \_\_\_\_\_

CHECK ALL THAT APPLY
----------------------

Appearance and Aesthetics

- Exterior
- Top section
- Oven interior
- Broiler pan set

Electrical Connection

- Correct voltage
- Grounded outlet
- Polarized outlet
- No GFCI

Installation

- Proximity to cabinets
- Level
- Backguard in place
- Ventilation system
- Read User Manual
- Review safety instructions

Gas Connection

- Verify fuel—\_\_\_\_ Nat \_\_\_\_ LP
- Gas shut-off present and accessible
- Supply line properly sized
- Supply pressure checked
- Operating pressure checked
- All connections checked for leaks

Ignition

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Flame Adjustment

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Air/Gas Mixture

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Valve Operation

- Top Burners
- Griddle
- Char Broiler
- Oven Burner
- Infrared Broiler

Controls

- Burner knobs
- Thermostats
- Convection oven fan & switch
- Oven light switch

Oven Door

- Alignment
- Door seal
- Hinges

MAIL-IN COPY